



SUNNICA ENERGY FARM

Preliminary Environmental Information Report

Appendix 11C: Construction Noise Modelling

Sunnica Ltd

AUGUST 2020



Quality information

Prepared by	Checked by	Verified by	Approved by
Various	Colin O'Connor Principal Acoustics Consultant	Yuyou Liu Acoustics Regional Manager	Neil Titley Technical Director

Revision History

Revision	Revision date	Details	Authorized	Name	Position
1	September 2020	For issue	YL	Yuyou Liu	Acoustics Regional Manager

Prepared for:
Sunnica Ltd.

Prepared by:
AECOM Infrastructure & Environment UK Limited
Unit 1 Wellbrook Court
Girton
Cambridge CB3 0NA
United Kingdom

T: +44 1223 488 000
aecom.com

© 2020 AECOM Infrastructure & Environment UK Limited. All Rights Reserved.

This document has been prepared by AECOM Infrastructure & Environment UK Limited ("AECOM") for sole use of our client (the "Client") in accordance with generally accepted consultancy principles, the budget for fees and the terms of reference agreed between AECOM and the Client. Any information provided by third parties and referred to herein has not been checked or verified by AECOM, unless otherwise expressly stated in the document. No third party may rely upon this document without the prior and express written agreement of AECOM.

11 Construction Noise Modelling

- 11.1.1 Due to the extent of the working areas it has been assumed that one of each construction plant item will be in operation at the closest approach to each of the identified sensitive receptors, continuously throughout a working day. It has been assumed that while there may be overlaps of work stages, noisy works associated with each stage affecting individual receptors would not overlap.
- 11.1.2 Plant schedules and source data for sound pressure/power levels used in the noise model are summarised below.

Table 11C-1 Sunnica West and East Site Plant Schedule for Construction Noise Model

<i>Plant</i>	<i>BS5228-1 ref.</i>	<i>Sound pressure level at 10m, L_{pA}</i>	<i>Sound power level, L_{wA}</i>	<i>Site preparation</i>	<i>Civil works</i>	<i>Structures</i>	<i>Panels</i>	<i>Electrical works</i>	<i>CCTV</i>	<i>Internal Substations</i>
Compact excavator	C3.20	68	96	0	1	1	1	1	1	0
Mobile crane	C4.55	70	98	1	0	0	0	1	0	1
Crawled Dozer	C2.13	78	106	1	1	0	0	0	0	1
Excavator	C2.17	70	98	1	1	0	0	0	0	1
Mini Excavator	C3.20	68	96	0	1	0	0	0	1	1
Push press piling rig	AECOM library data	66	94	0	0	1	0	0	0	0
Power generator	C4.76	61	89	1	0	0	0	0	0	1
Telehandler	C4.55	70	98	0	0	1	1	0	1	1
Truck	C4.5	63	91	0	1	0	0	0	0	1
Vibrating roller	C2.40	73	101	1	1	0	0	0	0	0
Wheeled Excavator	C2.8	68	96	0	1	0	0	0	0	1

Table 11C-2 Cable Route Plant Schedule for Construction Noise Model

<i>Plant</i>	<i>BS5228-1 ref.</i>	<i>Sound pressure level at 10m, L_{pA}</i>	<i>Sound power level, L_{wA}</i>	<i>Cable route</i>
360 Excavator	C2.17	70	98	1
Dumpers	C4.5	63	91	1
Sand Hopper and Plough	C10.5	80	108	1
Small plant and Cable Winch	C4.95	73	101	1

